TP#1 - ADDENDUM E-001

Project:	Drayton Valley Aquatics Centre	**WSP Ref.:**	191-12180-00
Date:	March 25, 2021	**Client No.:**	
To:	Chandos, Attn: Adam Mramor (amramor@chandos.com)		
Distribution:	WSP, Attn: Arshia Ahmed (arshia.ahmed@wsp.com) Altapro, Attn: Jefferey Tyson (jeffrey@altapro.ca) Altapro, Attn: Jake Gandy (jake@altapro.ca)		

TO ALL BIDDERS OF RECORD

General Notes:

1. *This Addendum is used prior to Tender Package #1 closing to provide for certain revisions as noted herein.*
2. *All such revisions will become part of the Work and the effects shall be included in the Tender Price.*

REFER TO DRAWING E100 – ELECTRICAL SITE PLAN

1. Underground conduit for future Electric Vehicle (EV) stalls shown as 27C to be revised to 53C. Total conduits crossing the Right of Way (ROW) will be 1x27C for lighting, 1x53C for EV charging station, 2x102C for SHAW/AXIA.

2. Where underground conduits pass throw Right of Way (ROW) on site plan and where minimum conduit clearance depth cannot be met, contractor to install pressure treated 2x6 plank where elevation breaches the proper depth. Coordinate conduits within ROW with Civil contractor as noted on drawings.

Issued by,

Daniel Tyrkalo C.E.T.
Electrical Engineering Technologist
Daniel.tyrkalo@wsp.com

DT/dt
Attachments

1200, 10909 Jasper Avenue NW
Edmonton, AB, Canada T5J 3L9

Tel: 1 780 410-6740
Fax: 1 780 449-4050
wsp.com